HASSAN DIVISION. [ADVERTISEMENTS.

The 17th December 1895.

Tenders are hereby invited for erecting rolled steel girder bridges on Saklespur-Arehalli road.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's office, between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the Contractor, and forwarded in sealed covers to the Executive Engineer before the 25th January 1896. The work should be completed by the end of June 1897.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 750 as earnest money.

6. Within eight days of the acceptance of the tender, the Contractor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the Contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

9. An approximate estimate of quantities and items of work required is given below. These quantities are not guaranteed.

10. Girders will be supplied.

Items.	Per.	Basavan-halli Bridge.	Kudra-halla Bridge.	Byadni-halla Bridge.	Total.
Concrete in surki mortar	C. ft.	1,424	1,752	1,499	4,675
Stone in surki mortar .. .	,,	6,850	8,591	7,901	23,342
Pointing in chunam	Sqrs.	11·45	16·93	12·51	40·89
Stone slabs .. .	C. ft.	23	34	23	80
Diverting stream and baling water.. ..		Lump sums in Rupees.			
Excavation	C. yds.	432	661	436	1,529
Steel girders	Cwt.	68¼	136½	68¼	273
Iron works		Lump sums in Rupees.			
Carriage from Bombay		Lump sums in Rupees.			
Do tools and plant		Lump sums in Rupees.			
Fitting girders		Lump sums in Rupees.			
Teakwood work	C. ft.	274	521	274	1,069
Painting iron works		Lump sums in Rupees.			
Tarring wood work		Lump sums in Rupees.			
Rough stone wings	C. yds.	112	40	112	264
Date stone		Lump sums in Rupees.			
Approach Roads.					
Excavation	C. yds.	2,900	..	..	2,900
Earthwork	C. yds.	17,186	2,813	4,952	24,951
Turfing	Sqrs.	475·20	144·90	115·20	735·30
Gravelling	C. yds.	812	267	375	1,454
Compensation .. .		Lump sums in Rupees.			
Cutting jungle		Lump sums in Rupees.			

The 10th January 1896.

Tenders are hereby invited for improving and extending the Taluk Cutcherry at Arkalgud.

2. The plans, estimates and schedule of rates and conditions, may be seen at the Executive Engineer's office between the hours of 11 A. M. and 4 P. M. daily.

forms of tender will be supplied on application, free of cost, by the Executive Engi-
ns should be filled in, signed by the Contractor and forwarded in sealed covers to the
gineer before the 25th January 1896, the work should be completed by the end of

4. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 150 as earnest money.

6. Within eight days of the acceptance of the tender, the Contractor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the Contractor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

9. An approximate estimate quantities of items of work required is given below. These quantities are not guaranteed.

Items.	Per.	Additions.	Improvements.	Total.
Excavating foundations	C. yds.	102	..	102
Filling in foundation with rough stone in clay	C. ft.	2,754	..	2,754
Burnt stone in chunam	,,	1,920	..	1,920
Brick in chunam	,,	4,015	2,641	6,656
Ditto in archwork	,,	16	..	16
Do stone slabs	Sq. ft.	749	..	749
Plastering with mortar	Sqrs.	66·59	36·00	102·59
Whitewashing	,,	52·09	..	52·09
Colorwashing	,,	14·50	..	14·50
White and colorwashing	Lump sums in Rupees.			
Honne wood work wrought and put up	C. ft.	201	..	201
Teakwood Do	,,	..	41	41
Do railings	R. ft.	52	..	52
Honne wood planking	Sq. ft.	78	..	78
Roofing with teak reepers 2″ × 1½″ corrugated iron, country tiles and chunam borders	Sqrs.	28·07	10·19	38·26
Teakwood doors and windows with iron bars pannelled ..	Sq. ft.	254	..	254
Repairing old doors and windows	Each	5	..	5
Dealwood ceiling tarred	Sqrs.	6×94	..	6×94
Burnt stone slab flooring with asphalting joists ..	,,	7·78	3·00	10·78
Concreting and plastering over	,,	10·66	5·00	15·66
Composition to keep off whiteants	,,	14·00	..	14·00
Matting with bamboo outer rind	,,	8·90	22·02	30·92
Pointing with mortar	,,	5·81	..	5·81
Perforated zinc sheeting	Sq. ft.	12	..	12
Painting doors and windows	Sqrs.	14·00	..	14·00
Filling basement with gravel	C. yds.	92	..	92
Dismantling the roof	Sqrs.	..	66·99	66·99
Do top of walls	C. ft.	..	1,064	1,064
Removing and re-setting old couples	Lump sums in Rupees.			
Re-roofing with Mangalore flat tiles double rows of reepers ..	Sqrs.	..	55·95	55·95
Ridging with old ridge tiles	R. ft.	..	300	300
Zinc gutters for valleys	Sq. ft.	..	184	184
Flagging with old slabs fixing finials (wooden)	No.	..	4	4
Repairing the compound wall	Lump sums in Rupees.			
Wood oiling	Sqrs.	..	32·00	32·00
Coping with brick in chunam for front walls over corrugated iron and pot tiled roofing	R. ft.	..	34	34

A. S. NAGAVKAR, *Ex. Engr.*